

E. NEW BUSINESS

4. Conditional Use Permit; PC Resolution 2024-02

Applicant: Tyonek Tribal Council

Request: Replace a failing culvert & add gravel to level the road within the 50-foot Habitat Protection district of Tyonek Creek

**Location: Timber Road / PIN 211-153-08
Tyonek Area**

Multi-Agency Permit Application



514 Funny River Road, Soldotna, AK 99669 • (907) 714-2460 • KenaiRivCenter@kpb.us

Applicant Information: (must be a landowner)

Name: Laurie Stuart
 Mailing: 101 W. Benson Blvd. Suite 501
Anchorage, AK 99503
 Phone: 907-278-1021
 Email: lstuart@ttcd.org

Agent Information: (if applicable)

Name: Irene Turletes
 Mailing: 582 E. 36th Ave, Suite 500
Anchorage, AK 99503
 Phone: 907-644-2099
 Email: irene.turletes@hdrinc.com

Project Location:

KPB Parcel ID: 21115308
 Physical Address: 61.04495°N, 151179923°W
 Subdivision: N/A
 Lot: N/A Block: N/A Addition/No.: N/A

Waterbody Information:

Waterbody: Tyonek Creek
 Riverbank: (*looking downstream*) Left Right
 River Mile: N/A

State of Alaska Permit Fees:

\$100 - ADNR State Parks Permit

KPB Permit Fees: (select one)

\$50 - KPB Habitat/Floodplain Permit
 \$300 - KPB Conditional Use/Floodway Permit

Project Information: New **OR** Extension/Amendment to **RC#** _____

Please select all activities that apply to your project:

- | | | |
|---|--|--|
| <input type="checkbox"/> Bank Stabilization | <input type="checkbox"/> Fish & Wildlife Management | <input type="checkbox"/> Road Construction |
| <input type="checkbox"/> Boat Launch | <input type="checkbox"/> Floating Dock | <input type="checkbox"/> Structure (Accessory) |
| <input type="checkbox"/> Bridge | <input type="checkbox"/> Fuel Storage Green Infrastructure | <input type="checkbox"/> Structure (Residential) |
| <input type="checkbox"/> Coir Logs | <input type="checkbox"/> In-Stream Structures (Weir) | <input type="checkbox"/> Spruce Tree Revetment |
| <input checked="" type="checkbox"/> Culvert | <input type="checkbox"/> Oil & Gas | <input type="checkbox"/> Stream Crossing |
| <input type="checkbox"/> ELP Structures | <input type="checkbox"/> On-Site Utilities | <input type="checkbox"/> Utility Line/Easement |
| <input type="checkbox"/> Equipment Stream Crossing | <input checked="" type="checkbox"/> Prior-Existing Structure | <input checked="" type="checkbox"/> Veg Mat |
| <input checked="" type="checkbox"/> Excavation, Dredging, and/or Fill | <input checked="" type="checkbox"/> Revegetation | <input checked="" type="checkbox"/> Vegetation Removal |
| <input type="checkbox"/> Fence Installation | <input checked="" type="checkbox"/> Root Wads | <input checked="" type="checkbox"/> Water Withdrawal |
| | | <input type="checkbox"/> Other: <small>See Attachment A Project Description to Support Kenai</small> |

Project Description: Provide a detailed description of your project; attach additional pages if necessary.

See Attachment A

Cost-Share: Is this project funded by the Cost-Share Program? Yes No

KPB Tax Credit Program: The Borough provides a tax credit as partial reimbursement for new habitat protection and restoration projects within 150 feet of anadromous streams. If you would like to pre-qualify for this credit, please provide your estimated project cost(s) below. Do not include grants or other funding assistance:

Elevated Light Penetrating Structures \$ _____
Habitat Restoration & Protection \$ _____
Green Infrastructure \$ _____
Other Activities \$ _____



Attachment A: Project Description
to Support Tyonek Creek Fish
Passage Project Kenai Peninsula
Borough Multi-Agency Permit
Application

November 2023

This page is intentionally left blank.

Contents

1	Introduction.....	2
1.1	Project Overview	2
1.2	Purpose and Need	2
1	Proposed Design.....	2
1.1	New Tyonek Creek Culvert Construction	3
1.2	New Tyonek Creek Channel and Bank Construction.....	3
1.1	Existing Tyonek Creek Culvert and Channel	4
1.2	Existing Cook Inlet Culverts	4
1.3	Excavation and Fill Quantities	4
2	Proposed Conservation Measures.....	5

1 Introduction

The Tyonek Tribal Conservation District (TTCD) in partnership with the United States Fish and Wildlife Service has requested assistance with the Tyonek Creek Fish Passage Project (Project). The Project includes the design and installation of a replacement roadway culvert at Tyonek Creek (247-20-10040) in Tyonek (Tyonek A-4 S011N011W14). The culvert spans Timber Road and is intended to improve fish passage and flood conveyance. The culvert passage project is located on Tyonek Native Corporation land. This Project description has been written to support the Kenai Peninsula Borough Multi-Agency permit application for the Project.

1.1 Project Overview

The existing Tyonek Creek Culvert is composed of a 72- by 60-inch corrugated, closed-bottom pipe arch buried beneath 20 feet of earth. Debris in combination with buoyant forces have damaged the culvert inlet. This damage has caused the inlet to cut away and shorten. As a result of being undersized and damaged, the culvert constricts flow from Tyonek Creek. This constriction is made worse by large debris that regularly get stuck at the inlet and create obstructions to fish passage. These observations were confirmed by site visits from the Alaska Department of Fish and Game in 2012 and 2016 and by HDR Engineering, Inc. and the Boutet Company in 2020.

Approximately 130 feet to the southeast of the Tyonek Creek culvert lies an overflow channel with one 60- and one 24-inch diameter culverts. During high flood events the overflow culverts provide relief to the Tyonek Creek culvert by diverting flows directly into Cook Inlet. However, these culverts are undersized and damaged from debris carried by overflow from Tyonek Creek, causing water to back up in the overflow channel.

Historical aerial imagery suggests the Tyonek River channel surrounding the culvert beneath Timber Road has been moved significantly since the 1970s due to the creation of a gravel pad immediately north of the culvert. The Project would reestablish the historical creek channel by rerouting the current creek, installing a new culvert beneath Timber Road to increase fish passage, and reconstruct the creek's banks. This design will meet the needs for fish passage design guidelines and is sized for flows above the 100-year event. The installation will accommodate normal sediment transport.

1.2 Purpose and Need

The historic changes and damage to Tyonek Creek has resulted in the creation of barriers to fish passage and flood hazards at flows under the five-year flood event. Flood events affecting Timber Road could cause significant delays in travel, services, and goods for Tyonek residents as the road experiences daily traffic and services the periodic barge shipments on the manmade landing south of the crossing. Additionally, flooding creates a risk of damage or destruction to utility lines in the vicinity of Tyonek Creek.

1 Proposed Design

The proposed design includes a 120-foot long 45'-10" x 22'-11" single radius multiplate arch pipe. The existing 72- by 60-inch culvert will remain during construction as a diversion culvert then filled-in-placed and decommissioned.

1.1 New Tyonek Creek Culvert Construction

The new culvert will span Timber Road approximately 50 feet south of the existing culvert location (Figure 1). The new Tyonek Creek culvert will happen exclusively in uplands and in the dry prior to flooding the new channel. The 45'-10" x 22'-11" single radius multiplate arch (Figure 2) will be placed on top of concrete footings that span the length of the culvert. The footings will be cast in place and buried at a minimum of 7 feet below the creek thalweg inside the culvert. Native material will be used to line the creek bed and will be covered by infill material. The infill will reach a minimum depth of 36 inches within the culvert. Infill material will be comprised of 50 percent coarse material (3 - 24 inches) and 50 percent fine material (<3 inches) by weight. Course material is made up of 50 percent Class III riprap and 50 percent Class II riprap. In total, the Project will use 300 cubic yards of riprap. Footer protection rock will fill the void inside of the culvert between the layer of native material and infill material and the footers. Fine material will fill the voids between footer protection rock. Additional segments of footer protection will extend 20 feet away from the north and south side of the inlet and outlet. These four segments will have a rip rap collar.

The creek bed constructed within the culvert will have an ordinary high water (OHW) wetted width of 35 feet and a thalweg depth of 3.5 feet. The low flow channel wetted width will be 10 feet with a 6 in thalweg. The low flow channel will be flush with the culvert at the inlet and outlet but meander within the culvert. Rip rap will be used for channel lining to resist erosion if grading of the creek crossings locally increases channel slope. Fill removed for the placement of the culvert and construction of the creek bed will be side cast immediately adjacent to the creek bank within the disturbance zone.

1.2 New Tyonek Creek Channel and Bank Construction

With the exception of construction associated with breaking the earthen dam separating the existing and new stream channel and the subsequent procedures to distribute substate fines, all creek bed and bank construction will happen prior to flooding the new channel. Culvert bedding will be used as backfill up to 30 feet away from the culvert inlet and 40 feet of the outlet and will be composed of the same material composition as that which is used within the culvert. Beneath the infill material there will be native material. Beyond these boundaries native material will be used as creek bed fill. The thalweg at the inlet will be at an elevation of 15.26 feet while the thalweg at the outlet is at an elevation of 14.64 feet with a grade through the culvert of -0.42 percent. The wetted width upstream and downstream of the culvert will vary. The upstream thalweg at OHW will be 2.5 feet. The low flow channel both upstream and downstream will be 10 feet with a thalweg depth of 6 inches. The downstream thalweg at OHW will have a depth of 5 feet. The proposed creek channel will diverge from the existing channel approximately 400 feet upstream of the existing structure and rejoin the existing creek channel 125 feet downstream of the proposed culvert.

Creek substrate will be placed in one or more layers with a layer depth less than 1.5 times the maximum dimension of the creek simulation rock, but no greater than four feet. Rocks are to be placed in a way to obtain a uniformly dense, compact, low permeability mass, matching the preexisting creek bed conditions. Bed materials will be compacted and water pressure, tamping rods, and other similar hand operated equipment will be used to force materials into voids.

Creek banks will be constructed to be uneven, protrude into the channel, and be rough in appearance with the top of the bank being relatively uniform. Rootwads will be placed in the creek substrate with boles oriented in the creek bed so that the top of the bole is approximately at the top of the low flow channel. Boles will be placed parallel to one another so that adjacent

root fans overlap a minimum of 3 feet. Header logs will be placed perpendicular to boles near the rootwad. Rebar will be used to stabilize the header log and bole in place, with each rebar extending 2 feet into the creek bed. The top of the rebar is to be bent over so that it doesn't slide down through the header log and bole. Creek substrate will be placed around logs behind rootwad fans with stone pieces locking header logs and boles into riprap mat. The empty space between logs behind the rootwad fans will be filled with salvaged creek bed material. Riprap will be used along the roadway embankment away from the active creek bed and be backfilled with unclassified material excavated from the new creek bed. Exposed riprap outside of the creekbank will be covered with onsite materials to promote revegetation.

Disturbed soil will be covered first in vegetated mat collected nearby the Project and cover the disturbed area to a thickness of 6 inches (Figure 1). In the absence of excess vegetative mats, native organic soils will be laid out to a thickness of six inches and seeded with a native mix. If additional topsoil is needed it will be imported to meet the desired soil thickness in disturbed areas.

Rewatering of the newly constructed Tyonek Creek will be done in a way that minimizes sediment movement downstream of the site. Prior to re-diverting full creek flows into the reconstructed channel and culvert, the channel will be wetted to wash fines into the creek bed. Sediment and turbid water at downstream end of reconstructed channel will be collected and pumped from the downstream end of channel back to upstream end of channel. This will be done until fines are washed into creek bed and water runs clear by using the minimum amount of water possible as determined by the construction contractor. After the initial sediment pulse is removed, the slowly dam separating the existing creek channel and new creek channel will be breached slowly to avoid a large pulse of water being sent through the newly constructed channel.

1.1 Existing Tyonek Creek Culvert and Channel

Once the earthen dam has been breached and flow diverted from the existing creek channel to the new creek channel construction will commence at the existing culvert and creek bed. Unused timber for rootwad banks will be piled within the old creek channel perpendicular to flow behind the armored rootwad bank or other location specified by construction personnel and be pinned in place with rebar. Fill accumulated from new creek channel excavation will also be used to backfill the channel and direct normal flows down the newly constructed channel. The culvert will be filled with a sand slurry and decommissioned.

1.2 Existing Cook Inlet Culverts

The existing 60-inch and 24-inch culverts directing overflow into the Cook Inlet will be removed and disposed of offsite. Material removed during the Project will be sidecast immediately adjacent to the culvert into uplands within the disturbance zone.

1.3 Excavation and Fill Quantities

Table 1 has been provided to fulfill the requirements of section 8 and 9 of the Kenai Peninsula Borough Multi-Agency Permit

Table 1 Excavation and Fill Quantities

Construction Type	Location	Construction Element	Length (ft)	Width (ft)	Depth (ft)	Total Cubic Yards
-------------------	----------	----------------------	-------------	------------	------------	-------------------

Dredging	Below OHW	N/A	0	0	0	0
Dredging Total	Below OHW	-	0	0	0	0
Excavation	Above OHW	New Creek Channel Excavation	650	Varies	Varies	20,650
Excavation Total	Above OHW	-	-	-	-	20,650
Fill	Above OHW	New Culvert Bedding	190	Varies	3	1,130
Fill	Above OHW	New Creek Bank	Varies	Varies	0.5	183
Fill Total	Above OHW	-	-	-	-	1,313
Fill	Below OHW	Existing Culvert Fill	6	5	5	4
Fill	Below OHW	Existing Creek Channel Fill	43	Varies	5	146
Fill Total	Below OHW	-	-	-	-	150

2 Proposed Conservation Measures

TTCD proposes to implement the following measures to avoid and/or mitigate potential impacts from the Project:



- Conduct existing creek bed construction in the dry and out of fish habitat
- Excavate the new creek bed in the dry and out of fish habitat
- Work below OHW in fish habitat will occur between May 15th and July 15th to minimize overlap with salmon run timing
- Equipment used for Project construction will be the minimum size necessary to perform the work in order to reduce impacts on creek banks and wetlands
- Excavated materials will be strategically placed to avoid creekbank disturbances
- Native material will be used when possible to reduce nonnative fill
- Rootwad construction will be done in a way that minimizes disturbance to stable embankment beyond necessary excavation limits required to place salvaged creek bed material and creek substrate material.
- Pumping procedures will be carried out in a way that reduces risks to fish health. Additionally, the pump will use a mesh size equal to or smaller than 3/32 inch or a profile bar and wedge wire with openings not greater than 1/16 inch. Approach velocities will not exceed a passive velocity of 0.2 feet feet/second or an active velocity of 0.4 feet/second
- Tree clearing will not occur between May 1st and July 15th to avoid impacts to nesting migratory birds

Figure Set

DRAFT












Tyonek Creek (Timber Road)
Fish Passage Project

0 100 Feet

HORIZONTAL DATUM: NAD83 AK State Plane Zone 4

-  Existing Culvert
-  Current Tyonek Creek Fill Area
-  Proposed Culvert
-  Culvert Bedding
-  New Tyonek Creek Channel
-  Current Tyonek Creek Channel
-  New Creek Bank
-  Disturbance Limits




APPLICANT: Tyonek Tribal Conservation District
 PERMIT: Kenai Peninsula Borough Multi-Agency
 WATERWAY: Tyonek Creek

LOCATION: 151.179°W 61.045°N

FIGURE 1


DATE: October 13, 2023



1
 D3

RECONSTRUCTED STREAM CHANNEL AT CULVERT INLET AND OUTLET
 NTS

DRAWING LOCATION: W:\WorkingFiles\Tyonek_Tribal_Connection\District\2022\TYONEK_CREEK\BC_CAD\TYONEK_CREEK_TILE_NEWER.dwg
 PLOT DATE: 11/28/23
 SCALE: N/A
 SHEET NO.: 11 OF 11
 DRAWN BY: [blank]
 CHECKED BY: [blank]



VICINITY MAP (NTS)

Tyonek



TRIBAL
CONSERVATION
DISTRICT



TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS

PREPARED BY

 THE BOUTET COMPANY, INC.
 601 E. 57TH PLACE #102
 ANCHORAGE, AK, 99518
 PH. 907-622-6776
 LICENSE NO. AECC957

ADF&G SITE # 20601540
 NOVEMBER 2023



ENGINEER'S CERTIFICATION:

TO THE BEST OF MY PROFESSIONAL KNOWLEDGE, JUDGEMENT, AND BELIEF THESE PLANS MEET APPLICABLE NRCS STANDARDS.



TIMOTHY J. ALKEY, P.E.
 DESIGN ENGINEER
 THE BOUTET COMPANY, INC.

11/28/23
 DATE

FILE: \\WASHFILE\FILES\TYONEK\TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK 11/28/2023 LAYOUT 11/28/2023 DESIGNED CBW CHECKED TJA DRAFTED CBW

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	A2	A4

SHEET INDEX	
SHEET NO.	CONTENTS
A1	TITLE SHEET
A2	NOTES, INDEX, LEGEND & ABBREVIATIONS
A3	PROJECT AREA AND STAGING/STORAGE AREAS
A4	SURVEY CONTROL
B1	TYPICAL SECTION
C1	ESTIMATE OF QUANTITIES
D1-D6	DETAILS AND STREAM CROSS SECTIONS
F1-F6	PLAN AND PROFILE
Q1-Q3	EROSION, SEDIMENT & POLLUTION CONTROL PLAN
P1	PROJECT PHOTOS
1-8	CONTECH BRIDGECOR SINGLE RADIUS ARCH SHOP DRAWINGS

ABBREVIATIONS

ADF&G	ALASKA DEPARTMENT OF FISH AND GAME
BW	BENCH MARK
BMP	BEST MANAGEMENT PRACTICE
BVCE	BEGIN VERTICAL CURVE ELEVATION
BVCS	BEGIN VERTICAL CURVE SEGMENT
CL	CENTERLINE
CMP	CORRUGATED METAL PIPE
CONST	CONSTRUCT
CSP	CORRUGATED STEEL PIPE
DET	DETAIL
D	DUCTILE IRON
EOP	END OF PROJECT
E	EASTING
ELEV	ELEVATION
EA	EASEMENT LINE
EST	ESTIMATED
ESCP	EROSION & SEDIMENT CONTROL PLAN
EVCE	END VERTICAL CURVE ELEVATION
EVCS	END VERTICAL CURVE SEGMENT
EW	EACH WAY
EX	EXISTING
FG	FINISHED GRADE
FL	FLOW LINE
GB	GRADE BREAK
HDPE	HIGH DENSITY POLYETHYLENE PIPE
HORZ	HORIZONTAL
HTC	HEAT TRACE CHANNEL
I	INVERT ELEVATION
INT	INTERSECTION
IN	IN ACCORDANCE WITH
AW	AKWIA PENINSULA BOROUGH
KFB	LENGTH
L	LINEAR FEET
LOC	LOCATION
LP	LOW POINT
LT	LEFT
LVC	LENGTH OF VERTICAL CURV
MAX	MAXIMUM
MD	MAXIMUM DRY DENSITY
ME	MATCH EXISTING
MFG	MANUFACTURED
MIN	MINIMUM
MON	MONUMENT
MSL	MEAN SEA LEVEL
N	NORTHING
NIC	NOT IN CONTRACT
NTS	NOT TO SCALE
OC	ON CENTER
OSH	ORDINARY HIGH WATER
OSHA	OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION
PAD	PAD ELEVATION
PCC	PORTLAND CEMENT CONCRETE
PC	POINT OF CURVATURE
PI	POINT OF INTERSECTION
PT	POINT OF TANGENCY
PUE	PUBLIC UTILITY EASEMENT
PVI	POINT OF VERTICAL INTERSECTION
R	RADIUS
RR	REMOVE AND REPLACE
ROW	RIGHT-OF-WAY
RP	RADIUS POINT
RT	RIGHT
REF	REFERENCE
RET	RETURN
S	SLOPE
SQ FT	SQUARE FOOT
STA	STATION
STD	STANDARD
SWPPP	STORM WATER POLLUTION PREVENTION PLAN
TAN	TANGENT
TEL	TELEPHONE
TBM	TEMPORARY BENCH MARK
TOE	TOE OF SLOPE
TOP	TOP OF SLOPE
TYP	TYPICAL

LEGEND

---	EXISTING GRAVEL ROAD SURFACE
---	NEW GRAVEL ROAD SURFACE
	INFILL MATERIAL
	EXISTING STREAM
	EXISTING WETLANDS
	SALVAGED VEGETATIVE MAT
	TOPSOIL AND SEED
	VEGETATIVE COLLAR
	ROOT WAD BANK RECONSTRUCTION
---	PROPOSED BOTTOM OF STREAM BANK
---	PROPOSED TOP OF STREAM BANK (OHW)
---	PROPOSED EDGE OF LOW FLOW CHANNEL
---	STREAM/ROADWAY CENTERLINE
---	EXISTING GRADE
---	FINISH GRADE PROFILE
---	CUT LIMIT
---	FILL LIMIT
---	EXISTING MINOR CONTOUR
---	EXISTING MAJOR CONTOUR
---	PROPOSED MINOR CONTOUR
---	PROPOSED MAJOR CONTOUR
---	PERIMETER CONTROL BMP
---	SLOPE INDICATOR
---	EXISTING SIGN
---	OVERHEAD ELECTRIC

CIVIL NOTES:

- CIVIL CONSTRUCTION SHALL BE COMPLETED IN ACCORDANCE WITH THE ALASKA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION 2020 EDITION, AS CURRENTLY AMENDED BY THE STANDARD MODIFICATIONS AND THESE CONSTRUCTION DRAWINGS.
- DRAWING SCALES ON SHEETS WITHIN THESE PLANS MAY VARY AND SHOULD BE NOTED PRIOR TO USE. THESE PLANS WERE CREATED FOR 11X17 PLAN SET AND AT A SPECIFIC DRAWING SCALE. ANY REPRODUCTION OR PUBLISHING OF THESE PLANS MAY RESULT IN DISTORTION OF SCALE AND SHALL BE VERIFIED PRIOR TO USE.
- SURVEY INFORMATION WAS PROVIDED BY THE BOUTET COMPANY. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE EXACT LOCATION OF ALL SITE FEATURES. IF CONDITIONS OTHER THAN THOSE SHOWN ON THE PLANS ARE ENCOUNTERED, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER.
- CONTRACTOR SHALL MAINTAIN "REDLINE" RECORD DRAWINGS ON A CLEAN SET OF CONSTRUCTION DRAWINGS. THE "REDLINES" SHALL BE KEPT CURRENT ON A DAILY BASIS AND SHALL BE AVAILABLE TO THE ENGINEER FOR INSPECTION ON THE JOBSITE.
- CONTRACTOR SHALL RECORD SURVEY NOTES FOR SUBMITTAL WITH AS-BUILT PLANS, INCLUDING HORIZONTAL AND VERTICAL LOCATIONS OF ALL UTILITIES ENCOUNTERED IN THE FIELD. CONTRACTOR SHALL RECORD ALL DEVIATIONS FROM THE PLANS.
- OWNER OBTAINED PERMITS OR STATUS THERE OF ARE SUPPLIED IN THE CONTRACT DOCUMENTS. CONTRACTOR SHALL ENSURE ALL PERMITS NECESSARY TO COMPLETE THE WORK ARE OBTAINED PRIOR TO EARTH WORK DISTURBING ACTIVITIES. CONTRACTOR SHALL ENSURE COMPLIANCE WITH ALL PERMITS UNTIL THE PROJECT HAS ACHIEVED FINAL ACCEPTANCE. CONTRACTOR SHALL OBTAIN AN ADF&G AQUATIC RESOURCE PERMIT FOR TRANSPORTING STRANDED FISH WITHIN THE PROJECT LIMITS.
- THESE NOTES CONTAIN INFORMATION NECESSARY FOR THE PROPER EXECUTION OF THE WORK CONTAINED ON THESE IMPROVEMENT PLANS. THESE NOTES APPLY TO ALL PLAN SHEETS. ADDITIONAL CONSTRUCTION NOTES MAY ALSO BE SHOWN ON INDIVIDUAL PLAN SHEETS. THE CONTRACTOR IS RESPONSIBLE TO READ AND COMPLY WITH ALL NOTES SHOWN ON THIS SET OF PLANS. THE TERM "CONTRACTOR" AS USED IN THESE NOTES AND ELSEWHERE IN THIS PLAN SET, MEANS THE GENERAL CONTRACTOR AND ALL SUBCONTRACTORS AND INDIVIDUALS AUTHORIZED TO PERFORM WORK SHOWN ON THESE IMPROVEMENT PLANS. THE CONTRACTOR IS RESPONSIBLE TO COMPLY WITH ALL NOTES APPLICABLE TO HIS/HER WORK. ALL CONTRACTORS ARE DIRECTED TO CONTACT THIS ENGINEER FOR ANY QUESTIONS REGARDING THE STATED OR IMPLIED MEANING OF ANY NOTE OR OTHER INFORMATION CONTAINED ON THESE IMPROVEMENT PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSURE THAT HIS/HER CONTRACT FOR SERVICES INCLUDES THE RESPONSIBILITIES DEFINED BY THE APPLICABLE NOTES.
- ALL QUANTITIES SHOWN HEREIN ARE APPROXIMATE AND DO NOT ACCOUNT FOR SWELL PRIOR TO COMPACTION OR WASTE. CONTRACTOR SHALL VERIFY ALL QUANTITIES.

EXISTING UTILITIES:

- PLANS MAY NOT SHOW ALL EXISTING UTILITIES WITHIN THE PROJECT AREA.
- CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND VERIFYING ALL UTILITIES AND PERFORMING ANY NECESSARY VERIFICATION PRIOR TO CONSTRUCTION. UTILITY LOCATING SHALL BE COMPLETED A MINIMUM OF 10 DAYS TO NO MORE THAN 20 DAYS PRIOR TO COMMENCEMENT OF WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF ALL EXISTING UTILITIES WITHIN THE LIMITS OF CONSTRUCTION, WHETHER OR NOT SAID UTILITIES ARE SHOWN ON THE PLANS. THIS RESPONSIBILITY INCLUDES CONTACTING UTILITY COMPANIES FOR LOCATIONS OR POTHOLES PRIOR TO CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES DURING CONSTRUCTION IS THE RESPONSIBILITY OF THE CONTRACTOR.
- THE CONTRACTOR SHALL PROTECT EXISTING UTILITIES TO REMAIN AND COORDINATE WITH UTILITY OWNERS FOR REQUIREMENTS FOR SHORING OR SUPPORTING UNDERMINED UTILITIES DURING CONSTRUCTION. SHORING/SUPPORTING OF UTILITIES SHALL BE CONSIDERED SUBSIDIARY TO THE CONTRACT AND WILL NOT BE MEASURED FOR PAYMENT.


EXCAVATION AND CULVERT INSTALLATION:



- CONTRACTOR SHALL EXERCISE EXTREME CAUTION AND OBSERVE ALL APPLICABLE OSHA REQUIREMENTS FOR WORKING IN CONFINED AREAS AND OPEN EXCAVATIONS.
- ORGANIC, OVER SATURATED OR NON-COMPACTABLE MATERIAL SHALL BE REMOVED FROM THE SUBGRADE TO A DEPTH TO BE DETERMINED BY THE ENGINEER. NO ORGANIC MATERIAL OR OTHER DELETERIOUS MATERIAL SHALL BE UTILIZED FOR BACKFILL.
- CONTRACTOR SHALL VERIFY INVERTS OF EXISTING CHANNEL AND ALL PROPOSED STRUCTURES PRIOR TO CONSTRUCTION. REPORT ANY DISCREPANCIES FROM THE PLANS IMMEDIATELY TO THE ENGINEER.
- FILL MATERIAL SHALL BE PLACED EVENLY AND SIMULTANEOUSLY IN LIFTS ON BOTH SIDES OF STRUCTURES, NOT TO EXCEED 8-INCHES IN DEPTH AND SHALL BE COMPACTED TO 95% MDD.
- INFILL MATERIAL SHALL BE INSTALLED IN THE PIPE ACCORDING TO THE PLANS.
- ALL VEGETATION IN THE AREAS NOT AFFECTED BY THE WORK SHALL BE PRESERVED AND PROTECTED BY THE CONTRACTOR. RESEED ALL DISTURBED AREAS IN CONFORMANCE WITH REVEGETATION PLANS ON SHEETS Q1, Q2, Q3, AND THE SWPPP.
- FINISH GRADE (FG) REPRESENTS THE ELEVATION OF THE FINISHED SURFACE. THIS INCLUDES LANDSCAPE AREAS, ROCK RIP-RAP SURFACE AND ELEVATION AT EXTERIOR OF STRUCTURE FOUNDATION, UNLESS OTHERWISE DENOTED ON DETAIL OR SPECIAL LABEL. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ADJUST SUBGRADE OR TOPSOIL TO ALLOW FOR FINISHED SURFACE MATERIAL DIMENSIONS.
- DEWATERING OF THE EXCAVATION MAY BE REQUIRED TO COMPLETE THE WORK. DISCHARGE OF DEWATERING PUMPS SHALL BE A MINIMUM OF 100' FROM STREAMS AND SHALL BE PROTECTED WITH BMP'S AS REQUIRED TO MINIMIZE SEDIMENT DISCHARGE INTO RECEIVING WATERS.

 THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-524-6778 LICENSE NO. AECC867 CONSULTANT	 TIMOTHY J. ALLEY CE 14388 PROFESSIONAL ENGINEER STATE OF ALASKA SEAL	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		NOTES, INDEX, LEGEND & ABBREVIATIONS

FILE: W:\ASL\FILES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG DATE/TIME: 11/28/2023 LAYOUT: CBW CHECKED: T.A. DRAFTED: CBW


NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	A3	A4




 THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-552-6776 LICENSE NO. AECC267 CONSULTANT	 SEAL	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		PROJECT AREA AND STAGING/STORAGE AREAS

FILE (E:\PROJECTS\TYONEK TRIBAL CONSERVATION DIST - 2020 PROGRAM SURVEYS\TYONEK CREEK\TYONEK_CREEK_SCD_B-30-23.DWG) DATE/TIME 11/05/2020 17:05:20:30 LAYOUT (DESIGNED) GRW (CHECKED) SA (DRAWN) GRW

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2020	A4	A4



Point #	Elevation	Northing	Eastng	Description
1	23.29	2575424.11	1431395.34	SET YPC
2	29.59	2575646.67	1431269.36	SET YPC
514	42.43	2575837.27	1431248.12	SET 6" NAIL




- Notes:**
1. Basis of Vertical Datum is NAVD 88.
 2. Elevations are expressed in feet.
 3. Coordinates are expressed in Alaska State Plane, Zone 4, in U.S. Survey Feet.


		TYONEK CREEK AT TYONEK TIMBER ROAD
		FISH PASSAGE IMPROVEMENTS
		SURVEY CONTROL DIAGRAM
CONSULTANT	SEAL	

FILE: \\WASL\FILES\TYONEK TRIBAL CONSERVATION DISTRICT\2021\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG DATE/TIME 11/28/2023 11:48:00 AM LAYOUT DESIGNED: CWB CHECKED: TJA DRAFTED: CWB

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	B1	B1





TIMBER ROAD RECONSTRUCTION TYPICAL SECTION (NTS)



BARGE LANDING RECONSTRUCTION TYPICAL SECTION (NTS)

TYPICAL SECTION NOTES:

1. CONTRACTOR SHALL CLEAR AND GRUB TO FILL/CUT CATCH LIMITS PLUS 2 FEET PER SIDE. SALVAGE GRUBBING MATERIAL FOR REUSE ON THE PROJECT. CLEARING LIMITS SHALL BE APPROVED BY THE ENGINEER PRIOR TO PERFORMING WORK.
 2. SEE CULVERT INSTALLATION DETAIL SHEET D1 FOR MATERIAL TO BE PLACED WITHIN CULVERT EXCAVATION LIMITS.
 3. OUTSIDE OF CULVERT EXCAVATION LIMITS, PLACE BORROW, TYPE B ON EXISTING ROAD BED AS NECESSARY TO CONSTRUCT NEW ROAD PROFILE.
 4. REUSE EXISTING VEGETATIVE MAT (GRUBBING) AS MUCH AS PRACTICABLE. PLACE 6-INCH TOPSOIL AND SEED AS NECESSARY AFTER REUSE OF GRUBBING MATERIAL.
 5. BACKFILL SHALL BE COMPACTED TO 95% MDD.
- *SEE SHEETS F4-F6 FOR TIMBER ROAD AND BARGE LANDING RECONSTRUCTION LAYOUT.

 THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-8778 LICENSE NO. AECC867 CONSULTANT	 SEAL	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		ROADWAY TYPICAL SECTION



FILE: \\NAS104\FILES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG
 DATE/TIME: 11/28/2023 11:28:23
 LAYOUT: []
 DESIGNED: []
 CHECKED: []
 TIA: []
 DRAFTED: []
 CW: []

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	C1	C1

ESTIMATE OF QUANTITIES				
ITEM NO.	ITEM DESCRIPTION	PAY UNIT	QUANTITY	NOTE
201	CLEARING	ACRE	1.7	NIC (WORK BY OTHERS)
	GRUBBING	ACRE	1.7	
202	REMOVAL OF CULVERT PIPE	LINEAR FOOT	82	
	DECOMMISSION EXISTING CULVERT PIPE	LINEAR FOOT	99	
203	UNCLASSIFIED EXCAVATION	CUBIC YARD	20,650	
	BORROW, TYPE B	CUBIC YARD	6,000	
305	STOCKPILE MATERIAL, TYPE B	CUBIC YARD	6,000	NIC (WORK BY OTHERS)
602	45'-10" X 22'-11" SINGLE RADIUS MULTI-PLATE ARCH PIPE (OWNER SUPPLIED)	LINEAR FOOT	120	
	45'-10" X 22'-11" SINGLE RADIUS MULTI-PLATE ARCH PIPE FOUNDATION	CUBIC YARD	123	
611	INFILL MATERIAL	CUBIC YARD	1,130	
	FOOTER PROTECTION MATERIAL	CUBIC YARD	650	
	VEGETATIVE COLLAR MATERIAL	CUBIC YARD	750	
615	FURNISH AND INSTALL SIGNPOST, BASE AND OWNER PROVIDED SIGN	EACH	1	
618	SEEDING	POUND	282	NIC (WORK BY OTHERS)
620	TOPSOIL	SQUARE YARD	7,832	
621	PLANTING TREES AND SHRUBS	EACH	765	NIC (WORK BY OTHERS)
623	VEGETATIVE MAT SALVAGE AND REPLANTING	SQUARE YARD	740	
640	MOBILIZATION AND DEMOBILIZATION	LUMP SUM	ALL REQ'D	
641	EROSION AND POLLUTION CONTROL ADMINISTRATION	LUMP SUM	ALL REQ'D	
	TEMPORARY EROSION AND POLLUTION CONTROL	LUMP SUM	ALL REQ'D	
642	CONSTRUCTION SURVEYING	LUMP SUM	ALL REQ'D	
643	TRAFFIC MAINTENANCE	LUMP SUM	ALL REQ'D	
671	ROOTWAD BANK RECONSTRUCTION	LINEAR FOOT	400	
	ROOTWAD HARVEST	EACH	150	NIC (WORK BY OTHERS)
	HEADER LOG HARVEST	EACH	150	NIC (WORK BY OTHERS)
672	STREAM DIVERSION & DEWATERING	LUMP SUM	ALL REQ'D	


ESTIMATE OF QUANTITIES NOTES:

1. THE ESTIMATE OF QUANTITIES IS PROVIDED FOR INFORMATIONAL PURPOSES ONLY TO DEMONSTRATE THE RELATIVE SCOPE AND MAGNITUDE OF THE PROJECT. BIDDERS SHALL CALCULATE QUANTITIES IN PREPARATION OF BIDS. DISCREPANCY BETWEEN THIS ESTIMATE AND FINAL QUANTITIES DURING CONSTRUCTION SHALL NOT BE A BASIS FOR A CLAIM.
2. WORK BY OTHERS: MULTIPLE WORK ITEMS WILL BE COMPLETED BY OTHERS PRIOR TO, DURING AND AFTER THE PROJECT. THE CONTRACTOR SHALL BE FAMILIAR WITH THE WORK DONE BY OTHERS AND COORDINATE AS REQUIRED. IF THE WORK OF THE CONTRACTOR IS DELAYED BECAUSE OF ANY ACTS OR OMISSIONS OF OTHERS, THE CONTRACTOR SHALL BE ENTITLED TO ADDITIONAL COMPENSATION AND/OR EXTENSION OF TIME FROM THE OWNER.

 THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-8778 LICENSE NO. AECC867 CONSULTANT	 TIMOTHY J. ALLEY P.E. LICENSE NO. 14388 PROFESSIONAL ENGINEER STATE OF ALASKA SEAL	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		ESTIMATE OF QUANTITIES

FILE: W:\ASSETS\FILES\TYONEK TRIBUTAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK TP 8-1423.DWG DATE/TIME: 11/28/2023 11:42:00 LAYOUT: DESIGNED: CWB CHECKED: TJA DRAFTED: CWB

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	D1	D6




1
D1 CULVERT INSTALLATION
NTS LOOKING UP STREAM

CULVERT INSTALLATION NOTES:

- CULVERT INFILL MATERIAL SHALL INCLUDE ONE PART OF COARSE AND ONE PART FINE MATERIAL MEETING THE GRADATIONS SHOWN HEREIN. COARSE MATERIAL IS MADE UP OF APPROXIMATELY 1 PART RIPRAP CLASS II AND 4 PARTS RIPRAP CLASS I.
- FOOTER PROTECTION ROCK SHALL INCLUDE 1 PART CLASS III RIP RAP AND 1 PART CLASS II RIPRAP. FILL ALL VOIDS WITH FINE MATERIAL.
- SALVAGE AND REUSE EXISTING STREAM BED MATERIAL WITHIN THE CUT LIMITS FOR USE AS FINE COMPONENT OF STREAM SUBSTRATE AT THE DIRECTION OF THE ENGINEER. IMPORTED MATERIAL SHALL BE USED IF SUFFICIENT QUANTITY OF EXISTING STREAM BED MATERIAL IS NOT AVAILABLE.
- STREAM SUBSTRATE MATERIAL SHALL BE INSTALLED IN STRUCTURES ACCORDING TO THE PLANS. MANUAL SHAPING OF THE STREAM CHANNEL IS REQUIRED.
- ENGINEER TO APPROVE MATERIALS AND METHOD FOR STREAM SUBSTRATE MATERIALS BEFORE MIXING AND PLACING MATERIAL IN CULVERT OR RECONSTRUCTED STREAM CHANNEL. NOTIFY THE ENGINEER AT LEAST 48 HOURS IN ADVANCE OF PLACING CULVERT INFILL MATERIAL.
- CONSTRUCT STREAMBED AND BANKS LEAVING A ROUGH, NON-UNIFORM SURFACE.
- CULVERT JOINTS SHALL BE SOIL TIGHT.
- SPRAY HIGH PRESSURE WATER ON ALL CULVERT INFILL MATERIAL AND FOOTER PROTECTION ROCK TO THOROUGHLY WASH FINES INTO THE STREAMBED PRIOR TO DIVERTING STREAM INTO NEWLY CONSTRUCTED CHANNEL. FINES SHOULD BE WASHED IN UNTIL WATER POOLS ON SURFACE. ADDITIONAL FINES MAY BE REQUIRED DURING THIS PROCESS.
- TRENCH WALL SLOPES SHALL CONFORM TO OSHA SAFETY STANDARDS.
- MATERIAL WITHIN A FOOT OF THE EXTERIOR PIPE SURFACE SHALL BE THREE INCH MINUS. REFER TO CONTECH'S STRUCTURAL SHEETS.
- BACKFILL SHALL BE COMPACTED TO 95% MDD.

TYONEK CREEK CULVERT INFILL MATERIAL

COARSE MATERIAL 50% BY WEIGHT		FINE MATERIAL 50% BY WEIGHT	
SIZE	% PASSING	SIZE	% PASSING
24"	100	3"	100
20"	98	2"	82
16"	90	1.5"	71
12"	83	1"	58
10"	72	0.75"	50
8"	40	0.5"	41
5"	16	#4	25
3"	8	#10	16
-	-	#40	7
-	-	#100	4
-	-	#200	3




1
D2 FOOTING CROSS SECTION
NTS

<p>THE BOUTLET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99516 PH: 907-522-8778 LICENSE NO. AEC0687</p>		TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		CULVERT INSTALLATION DETAILS

FILE: \\WASLAF\FILES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG
 DATE/TIME 11/28/2023 11:28:20
 LAYOUT
 DESIGNED CBW
 CHECKED TJA
 DRAFTED CBW

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	D2	D6



1
D2
RECONSTRUCTED STREAM CHANNEL UPSTREAM OF CULVERT STA 20+40 TO STA 23+94
NTS LOOKING DOWN STREAM


- BANK RECONSTRUCTION NOTE:**
- SEE SHEET D6 FOR BANK RECONSTRUCTION DETAILS
 - STREAM BOTTOM OUTSIDE OF CULVERT TO CONSIST OF NATIVE, INSITU GRAVELS. EXCAVATE TO LIMITS SHOWN.
 - PLANT 2 SAPPLINGS 1.5' TO 5.5' TALL FOR EVERY TREE CUT DOWN AS REQUIRED BY KPB PERMITS. SEE SHEET Q2 FOR SAPLING ESTIMATE TABLE FOR APPROXIMATE QUANTITY OF SAPPLINGS. REFER TO PAGES 19-20 OF ADFG'S 2005 STREAMBANK REVEGETATION AND PROTECTION GUIDE FOR VEGETATIVE MAT SALVAGE AND/OR HARVEST AND REPLANTING.
 - REFER TO PAGES 19-20 OF ADFG'S 2005 STREAMBANK REVEGETATION AND PROTECTION GUIDE FOR VEGETATIVE MAT SALVAGE AND/OR HARVEST AND REPLANTING. IF MAT IS NOT PLACED IN FINAL POSITION WITHIN 24 HOURS OF HARVEST STOCKPILE ON PLASTIC SHEETING, ROOTS DOWN AND SURROUND WITH SOIL TO PREVENT ROOTS AROUND THE EDGES FROM DRYING. REGULARLY WATER THE VEGETATIVE MAT UNTIL SITE IS PREPARED FOR PLANTING.
 - REFER TO PAGES 70-75 OF ADFG'S 2005 STREAMBANK REVEGETATION AND PROTECTION GUIDE FOR ROOT WADS.
 - SPRAY HIGH PRESSURE WATER ON ALL CULVERT INFILL MATERIAL AND FOOTER PROTECTION ROCK TO THOROUGHLY WASH FINES INTO THE STREAMBED PRIOR TO DIVERTING STREAM INTO NEWLY CONSTRUCTED CHANNEL. FINES SHOULD BE WASHED IN UNTIL WATER POOLS ON SURFACE. ADDITIONAL FINES MAY BE REQUIRED. STREAM SHALL NOT BE RE-DIVERTED INTO CULVERT UNTIL ENGINEER HAS APPROVED BED MATERIALS ARE SUFFICIENTLY SEALED.
 - REFER TO PAGES 34-37 OF ADFG'S 2005 STREAMBANK REVEGETATION AND PROTECTION GUIDE FOR LIVE STAKING, PLANTING AND SPACING OF SAPPLINGS.
 - REFER TO PAGES 26-27 ADFG'S 2005 STREAMBANK REVEGETATION FOR SELECTION OF SAPLING PLANT SPECIES. ENGINEER SHALL APPROVE SAPLING SPECIES PRIOR TO PLANTING.
 - VEGETATIVE MAT SHOULD BE AT LEAST 6 INCHES THICK. IF LOSS OF TOPSOIL DURING HANDLING AND STOCKPILING REDUCES MAT THICKNESS TO LESS THAN 6 INCHES, PLACE ADDITIONAL TOPSOIL BENEATH MAT TO BRING TOTAL THICKNESS OF VEGETATIVE MAT TO 6 INCHES.
 - THE CONTRACTOR MAY INSTALL THE ROOTWADS IN THE WET GROUND BUT SHALL USE TEMPORARY BALLAST AS NEEDED WHILE INSTALLING TO RESIST BUOYANCY AND ENSURE THE FINAL ELEVATIONS ARE MET.

- CROSS SECTION NOTE:**
- THE ROOTWAD CONSTRUCTION DOES NOT START UNTIL STREAM STATION 21+17.



<p>THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-8778 LICENSE NO. AECC867</p> <p>CONSULTANT</p>		TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		BANK RECONSTRUCTION AT CULVERT INLET DETAILS

FILE: \\WASL\FILES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK TP 81423.DWG DATE/TIME 11/28/2023 11:40:00 AM LAYOUT DESIGNED: CWB CHECKED: TJA DRAFTED: CWB

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	D3	D6




1
 D3
 RECONSTRUCTED STREAM CHANNEL AT CULVERT INLET AND OUTLET
 NTS LOOKING DOWN STREAM


 THE BOUTLET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-8778 LICENSE NO. AECC687 CONSULTANT	 SEAL	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		BANK RECONSTRUCTION AT CULVERT INLET DETAILS

FILE: W:\ASSETS\FILES\TYONEK TRIBUTAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK TP 81423.DWG DATE/TIME: 11/28/2023 11:48:00 LAYOUT: DESIGNED: CWB CHECKED: TJA DRAFTED: CWB



NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	D4	D6



1
D4
SIMULATED STREAM CHANNEL PLAN
NTS




2
D4
SIMULATED STREAM CHANNEL PROFILE STA 23+94 TO STA 25+23
NTS LOOKING DOWN STREAM

 THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-8778 LICENSE NO. AECC687 CONSULTANT	 SEAL	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		BANK RECONSTRUCTION AT CULVERT DETAILS

FILE: W:\ASSETS\TYONEK TRIBUTARY\TYONEK CREEK\TBC CAD\TYONEK CREEK TP 81423.DWG
 DATE/TIME: 11/28/2023 11:28:23
 LAYOUT: []
 DESIGNED: []
 CHECKED: []
 T.A.
 DRAFTED: []
 C.W.

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	D5	D6



1
 D5
 RECONSTRUCTED STREAM CHANNEL DOWNSTREAM OF CULVERT STA 25+23 TO STA 26+10
 NTS LOOKING DOWN STREAM


BANK RECONSTRUCTION NOTE:

- SEE SHEET D6 FOR BANK RECONSTRUCTION DETAILS
- STREAM BOTTOM OUTSIDE OF CULVERT TO CONSIST OF NATIVE, INSITU GRAVELS. EXCAVATE TO LIMITS SHOWN.
- PLANT 2 SAPLINGS 1.5' TO 5.5' TALL FOR EVERY TREE CUT DOWN AS REQUIRED BY KPB PERMITS. SEE SHEET Q2 FOR SAPLING ESTIMATE TABLE FOR APPROXIMATE QUANTITY OF SAPLINGS. REFER TO PAGES 19-20 OF ADFG'S 2005 STREAMBANK REVEGETATION AND PROTECTION GUIDE FOR VEGETATIVE MAT SALVAGE AND/OR HARVEST AND REPLANTING.
- REFER TO PAGES 19-20 OF ADFG'S 2005 STREAMBANK REVEGETATION AND PROTECTION GUIDE FOR VEGETATIVE MAT SALVAGE AND/OR HARVEST AND REPLANTING. IF MAT IS NOT PLACED IN FINAL POSITION WITHIN 24 HOURS OF HARVEST STOCKPILE ON PLASTIC SHEETING, ROOTS DOWN AND SURROUND WITH SOIL TO PREVENT ROOTS AROUND THE EDGES FROM DRYING. REGULARLY WATER THE VEGETATIVE MAT UNTIL SITE IS PREPARED FOR PLANTING.
- REFER TO PAGES 70-75 OF ADFG'S 2005 STREAMBANK REVEGETATION AND PROTECTION GUIDE FOR ROOTWADS.
- SPRAY CLEAN WATER ON ALL CULVERT INFILL MATERIAL TO THOROUGHLY WASH FINES INTO THE STREAMBED PRIOR TO DIVERTING STREAM INTO NEWLY CONSTRUCTED CHANNEL.
- REFER TO PAGES 34-37 OF ADFG'S 2005 STREAMBANK REVEGETATION AND PROTECTION GUIDE FOR LIVE STAKING, PLANTING AND SPACING OF SAPLINGS.
- REFER TO PAGES 26-27 ADFG'S 2005 STREAMBANK REVEGETATION FOR SELECTION OF SAPLING PLANT SPECIES. ENGINEER SHALL APPROVE SAPLING SPECIES PRIOR TO PLANTING.

<p>THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-6776 LICENSE NO. AECC657</p>		TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		BANK RECONSTRUCTION AT CULVERT OUTLET DETAILS

FILE: \\WASLAFILES\TYONEK TRIBUTAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG
 DATE/TIME: 11/28/2023 11:40:00
 LAYOUT: CBW CHECKED: TJA DRAFTED: CBW


NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	D6	D6




ROOTWAD NOTES:

1. ROOTWAD FAN AND STAGGER AS SHOWN IS APPROXIMATE AND SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER. OVERLAP WILL BE BASED ON ACTUAL FAN DIMENSION. PLACEMENT SHALL FOLLOW THE ALASKA DEPARTMENT OF FISH AND GAME RECOMMENDATIONS IN THE PUBLICATION "STREAMBANK REVEGETATION AND PROTECTION, A GUIDE FOR ALASKA, 2005".
2. ROOTWAD FAN TO BE A MINIMUM OF 6- FEET IN DIAMETER. THE FANS NEED TO BE SHINGLED AND OVERLAPPING AT A MINIMUM 3" ACCORDING TO ADFG DESIGN MANUAL.
3. HEADER LOGS TO BE A MINIMUM OF 10-INCHES IN DIAMETER AND MIN 10' LONG.
4. BOLES TO BE A MINIMUM OF 12-INCHES IN DIAMETER AND 15-FOOT IN LENGTH
5. PIN LOGS TOGETHER WITH #6 REBAR PLACED IN 3/4" Ø PILOT HOLE. PINS TO BE DRIVEN FLUSH WITH LOG FACE. EMBED REBAR 2-FOOT MINIMUM INTO NATIVE SOIL.
6. REFER TO PAGES 70-75 OF ADFG'S 2005 STREAMBANK REVEGETATION AND PROTECTION GUIDE FOR ROOT WADS.


1 ROOTWAD BANK RECONSTRUCTION
D6 NTS




3 ROOTWAD BANK UP STREAM TIE BACK
D6 NTS



2A BRUSH MATRIX
D6 NTS



2B BRUSH MATRIX CROSS SECTION
D6 NTS




4 ROOTWAD BANK DOWN STREAM TIE BACK
D6 NTS



<p>THE BOUTLET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-6776 LICENSE NO. AECC857</p> <p>CONSULTANT</p>		TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		STABILIZATION DETAILS

FILE: \\WASILAFILES\TYONEK TRIBAL CONSERVATION DISTRICT\2023\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG DATE/TIME 11/28/2023 11:28:23 LAYOUT DESIGNED: CBW CHECKED: TJA DRAFTED: CBW

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	F1	F6





- DEMOLITION PLAN NOTES:**
- TOTAL AREA OF DISTURBANCE IS 1.68 ACRES.
 - LIMITS OF DISTURBANCE SHOWN ARE APPROXIMATE BASED ON FIELD OBSERVATIONS. ACTUAL LIMITS SHALL BE DELINEATED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER PRIOR TO CLEARING AND GRUBBING.
 - THE STREAM CHANNEL AND VEGETATION IN AREAS NOT EFFECTED BY WORK SHALL BE PROTECTED AND PRESERVED BY THE CONTRACTOR. ALL DISTURBED AREAS IN CONFORMANCE WITH THE REVEGETATION PLAN.

 THE BOUTLET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-6776 LICENSE NO. AECC267 CONSULTANT	 SEAL	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		DEMOLITION PLAN


FILE: W:\ASSETS\TYONEK TRIBAL CONSERVATION DISTRICT\2021\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG
 DATE/TIME: 11/28/2023 11:28:23 AM
 LAYOUT: 11/28/2023 11:28:23 AM
 DESIGNED: CBW
 CHECKED: TJA
 DRAFTED: CBW

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	F2	F6



LINE TABLE		
LINE #	LENGTH	DIRECTION
L1	117.51	S59° 33' 21.19"E
L2	8.54	S57° 23' 40.57"W
L3	71.42	S86° 30' 23.81"W
L4	61.93	S74° 49' 08.60"W



CURVE TABLE					
CURVE #	LENGTH	RADIUS	DELTA	CHORD DIRECTION	CHORD LENGTH
C1	255.15	125.00	116.95	S1° 04' 50"E	213.10
C2	31.31	47.00	38.17	S76° 28' 48"W	30.74
C3	61.87	47.00	75.43	S57° 51' 08"W	57.50
C4	57.92	50.00	66.37	S53° 19' 22"W	54.73
C5	12.24	60.00	11.69	S80° 39' 46"W	12.22



<p> THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-6776 LICENSE NO. AECC067 </p>		TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		CULVERT AND STREAM PLAN AND PROFILE


FILE: W:\ASSETS\TYONEK TRIBUTAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG
 DATE/TIME: 11/28/2023 11:28:20.33
 LAYOUT
 DESIGNED: CBW
 CHECKED: TJA
 DRAFTED: CBW

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	F3	F6



LINE #	LENGTH	DIRECTION
L1	117.51	S59° 33' 21.19"E
L2	8.54	S57° 23' 40.57"W
L3	71.42	S86° 30' 23.81"W
L4	61.93	S74° 49' 08.60"W

CURVE #	LENGTH	RADIUS	DELTA	CHORD DIRECTION	CHORD LENGTH
C1	255.15	125.00	116.95	S1° 04' 50"E	213.10
C2	31.31	47.00	38.17	S76° 28' 48"W	30.74
C3	61.87	47.00	75.43	S57° 51' 08"W	57.50
C4	57.92	50.00	66.37	S53° 19' 22"W	54.73
C5	12.24	60.00	11.69	S80° 39' 46"W	12.22



THE BOUTET COMPANY, INC.
 801 E. 57TH PLACE #102
 ANCHORAGE, AK 99518
 PH: 907-552-6776
 LICENSE NO. AECC687
 CONSULTANT




STATE OF ALASKA
 40th
 TIMOTHY J. ALLEY
 CE 14388
 PROFESSIONAL ENGINEER
 SEAL

TYONEK CREEK (TIMBER ROAD)
FISH PASSAGE IMPROVEMENTS

CULVERT AND STREAM
PLAN AND PROFILE

FILE: W:\ASSTLAFILES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG DATE/TIME: 11/28/2023 11:42:00 LAYOUT: DESIGNED: CBW CHECKED: TJA DRAFTED: CBW



NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	F4	F6





<p>THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-524-8778 LICENSE NO. AECC657</p> <p>CONSULTANT</p>	<p>STATE OF ALASKA 40th TIMOTHY J. ALLEY P.E. 14388 PROFESSIONAL ENGINEER MAYNARD, ALASKA</p> <p>SEAL</p>	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		ROAD PLAN AND PROFILE

FILE \\WASLAF\FILES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG DATE/TIME 11/28/2023 11:42:23 LAYOUT DESIGNED CWB CHECKED TJA DRAFTED CWB




NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	F5	F6





 THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-8778 LICENSE NO. AECC857	 SEAL	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		ROAD PLAN AND PROFILE

FILE: W:\ASSETS\FILES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK F6 81423.DWG DATE/TIME: 11/28/2023 LAYOUT: DESIGNED: CW: CHECKED: TJA: DRAFTED: CW:


NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	F6	F6




 THE BOUTET COMPANY, INC. 801 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-6778 LICENSE NO. AECC0857 CONSULTANT	 SEAL	TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		ROAD PLAN AND PROFILE

FILE: \\WASLAPLES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG DATE/TIME 11/28/2023 11:42:10 LAYOUT DESIGNED CWB CHECKED TJA DRAFTED CWB

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	Q1	Q3



- TEMPORARY ESCP NOTES:**
1. INSTALL TEMPORARY PERIMETER CONTROL IN ACCORDANCE WITH THE APPROVED SWPPP AND PRIOR TO GROUND DISTURBANCE.
 2. ADJUST PERIMETER CONTROL AS NEEDED TO MINIMIZE EROSION AND SEDIMENT DISCHARGE TO RECEIVING WATERS.
 3. FOR TEMPORARY AND/OR FINAL STABILIZATION WATTLES SHALL NOT CONTAIN PLASTIC WEBBING.
 4. CONTRACTOR SHALL MINIMIZE THE AMOUNT OF DISTURBED AREA OPEN TO EROSION AT ANY ONE TIME.
 5. PERIMETER CONTROLS SHALL BE INSTALLED PRIOR TO EARTH DISTURBING ACTIVITIES. UTILIZE VEGETATED BUFFERS, FILTER SOCK OR BURLAP WATTLES, AND/OR SILT FENCE. APPROXIMATE LOCATIONS AS SHOWN ON THE PLAN SHEETS DEPENDS ON THE METHOD OF WORK. "FINISH AS YOU GO" STABILIZATION SHALL OCCUR AS EACH EARTH DISTURBING ACTIVITY IS COMPLETED IN ANY AREA. TEMPORARY STABILIZATION SHALL BE INSTALLED UNTIL PERMANENT STABILIZATION IS ACHIEVED.
 6. STOCKPILE AND STAGING LOCATION SHALL BE RECLAIMED TO THEIR ORIGINAL CONDITION. NO STOCKPILES OR STAGING AREAS ARE ALLOWED IN WETLANDS.
 7. ALL STOCKPILES OR ERODIBLE MATERIAL SHALL HAVE PERIMETER CONTROLS IN PLACE.
 8. THE WORK AREA SHALL BE ISOLATED FROM THE FLOWING WATER. VEHICLES OR EQUIPMENT OPERATION SHALL BE MINIMIZED IN FLOWING WATER.



TEMPORARY ESCP

THE BOUTET COMPANY, INC.
601 E. 57TH PLACE #102
ANCHORAGE, AK 99518
PH: 907-522-6776
LICENSE NO. AECC267


TYONEK CREEK (TIMBER ROAD)
FISH PASSAGE IMPROVEMENTS

TEMPORARY EROSION, SEDIMENT &
POLLUTION CONTROL PLAN

FILE: \\WASILEWLES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG DATE/TIME: 11/28/2023 11:28:00 LAYOUT: DESIGNED: CWB CHECKED: TJA DRAFTED: CWB

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	Q2	Q3

- FINAL STABILIZATION NOTES:**
1. INSTALL FINAL STABILIZATION BMP'S AS SOON AS PRACTICABLE AFTER COMPLETION OF THE WORK.
 2. INSTALL SALVAGED VEGETATIVE MAT ALONG STREAM FIRST WORKING AWAY. WHEN SALVAGED VEGETATIVE MAT IS DEPLETED, STABILIZE REMAINING AREA WITH 6" TOPSOIL AND SEED.
 3. PLANT SAPLINGS PER THE REQUIREMENTS WITHIN KPB PERMITS. SELECT SAPLING SPECIES AND SPACING PER ADF&G'S STREAMBANK REVEGETATION AND PROTECTION GUIDE. PLANT TREES AT A DENSITY OF 17 SAPLINGS PER 1000 SQ FT.
 4. INSTALL RECP ON ALL TOPSOILED SLOPES GREATER THAN 5' IN LENGTH AND 2:1 OR STEEPER.
 5. PLACE RIPRAP, CLASS I, 2' IN DEPTH FROM PIPES' INLETS AND OUTLETS EXTENDING 5' UP THE SLOPE FROM WATER LINE.
 6. ROOTWAD BANK RECONSTRUCTION LENGTHS SHALL BE AS SHOWN OR TO CUT LIMITS, WHICHEVER IS GREATER.
 9. SPRAY HIGH PRESSURE WATER ON ALL CULVERT INFILL MATERIAL TO THOROUGHLY WASH FINES INTO THE STREAMBED PRIOR TO DIVERTING STREAM INTO NEWLY CONSTRUCTED CHANNEL.
 10. PLACE ROLLED EROSION CONTROL PRODUCT (RECP) ON ALL TOPSOIL AND SEEDED SLOPES 2: TO 1 OR STEEPER. HYDROSEEDING WITH FLEX TERRA FLEXIBLE GROWTH MEDIUM MAY BE SUBSTITUTED FOR RECP. APPLY PER MANUFACTURER'S RECOMMENDATIONS.
 11. PLACE SLASH AND/OR SALVAGED NATIVE WOODY MATERIAL ON REVEGETATED SLOPES TO AIDE IN RESEEDING EFFORTS AND ESTABLISHMENT OF RIPARIAN AREA HABITAT.
 12. BANKS SHOULD TRANSITION TO TIE INTO EXISTING NATURAL CHANNEL BANKS.
 13. CONTRACTOR SHALL RETAIN ALL RIPRAP, WOODY DEBRIS LOGS AND ROOT WADS NOT NEEDED FOR CONSTRUCTION UNTIL ACCEPTANCE OF THE STREAMBED. CONTRACTOR COORDINATE WITH ENGINEER FOR USE OF RETAINED EXTRA MATERIAL FOR USE AS MINOR INSTREAM HABITAT FEATURES SUCH AS, BUT NOT LIMITED TO:
 - A. 2' DIAMETER OR GREATER ROCK
 - B. ROOT WAD HALF BURIED
 - C. 4" MIN DIAMETER LOG PARTIALLY BURIED




SAPLING QUANTITY ESTIMATE TABLE	
CULVERT LOCATION	NUMBER OF SAPLINGS
TYONEK CREEK	765

- SAPLING NOTES:**
1. CONTRACTOR SHALL PROVIDE BOITED SAPLINGS AT A RATE OF 2 SAPLINGS MINIMUM FOR EACH TREE CLEARED PER KENAI PENINSULA BOROUGH (KPB) PERMITS.
 2. SAPLING SPECIES SHALL BE COTTONWOOD AND ALDER. SPACE PLANTINGS PER ADF&G'S STREAMBANK REVEGETATION GUIDE. PLANT SAPLINGS AT AN APPROXIMATE DENSITY OF 17 SAPLINGS PER 1,000 SF.
 3. PLANT TREES A MINIMUM OF FIVE FEET APART.

LEGEND

- INFILL MATERIAL
- EXISTING STREAM
- EXISTING WETLANDS
- SALVAGED VEGETATIVE MAT
- TOPSOIL AND SEED
- VEGETATIVE COLLAR
- ROOT WAD BANK RECONSTRUCTION
- PROPOSED BOTTOM OF STREAM BANK
- PROPOSED TOP OF STREAM BANK (OHW)
- PROPOSED EDGE OF LOW FLOW CHANNEL
- CUT LIMIT
- FILL LIMIT
- EXISTING MINOR CONTOUR
- EXISTING MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- PROPOSED MAJOR CONTOUR
- PERIMETER CONTROL BMP




FINAL STABILIZATION PLAN

<p>THE BOUTLET COMPANY, INC. 601 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-522-6776 LICENSE NO. AECC367</p> <p>CONSULTANT</p>		TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS
		EROSION, SEDIMENT & POLLUTION CONTROL PLAN FINAL STABILIZATION PLAN


FILE: \\WASHFILE\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG
 DATE/TIME: 11/28/2023 11:40:00
 LAYOUT: CEW
 DESIGNED: CEW
 CHECKED: TJA
 DRAFTED: CEW

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	Q3	Q3




SILT FENCE NOTES:


1. INSTALLATION AND APPLICATION SHALL BE IN ACCORDANCE WITH THIS DETAIL AND PER THE MANUFACTURER'S RECOMMENDATION.
2. SILT FENCE FABRIC SHALL BE OVERLAPPED 6" AT FENCE SUPPORTS.
3. SILT FENCE FABRIC SHALL BE TAUT, NOT LOOSE OR FOLDED.
4. THE CONTRACTOR SHALL INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT.
5. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.




1 SUPER SACK DAM
Q3 NTS




BACKFILL ALTERNATE



TRENCH ALTERNATE



BACKFILL CROSS SECTION





TRENCH CROSS SECTION

1. FENCE SHALL BE PLACED AT LEAST 5' FROM THE TOE OF EMBANKMENT OR EXCAVATION AREAS, OR AS DIRECTED BY THE ENGINEER.
2. ACCUMULATION OF SEDIMENT BEHIND SILT FENCE SHALL BE REMOVED WHEN DEPTH REACHES 12". REMOVED SEDIMENT SHALL BE DEPOSITED IN AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.

SHEET NOTES:

1. SILT FENCE MAY BE SUBSTITUTED FOR WATTLES AS APPROVED BY THE ENGINEER.
2. WATTLES FOR TEMPORARY AND/OR FINAL STABILIZATION SHALL NOT CONTAIN PLASTIC WEBBING.


 THE BOUTET COMPANY, INC.
 601 E. 57TH PLACE #102
 ANCHORAGE, AK 99518
 PH: 907-522-6776
 LICENSE NO. AECC0367
 CONSULTANT


 SEAL

TYONEK CREEK (TIMBER ROAD)
FISH PASSAGE IMPROVEMENTS

EROSION, SEDIMENT &
POLLUTION CONTROL DETAILS

FILE: \\WASL\FILES\TYONEK TRIBAL CONSERVATION DISTRICT\2022\TYONEK CREEK\TBC CAD\TYONEK CREEK FP 81423.DWG DATE/TIME 11/28/2023 LAYOUT DESIGNED CBW CHECKED TJA DRAFTED CBW

NO.	DATE	REVISION	STATE	PROJECT DESIGNATION	YEAR	SHEET NO.	TOTAL SHEETS
			ALASKA		2023	P1	P1



EXISTING CULVERT INLET



EXISTING CULVERT OUTLET



BARGE LANDING FACING NORTH TOWARD PROJECT




STAGING AREA FACING NORTH FROM END OF PROJECT


<p>THE BOUTET COMPANY, INC. 601 E. 57TH PLACE #102 ANCHORAGE, AK 99518 PH: 907-552-6776 LICENSE NO. AECC687</p>		<p>TYONEK CREEK (TIMBER ROAD) FISH PASSAGE IMPROVEMENTS</p>
<p>CONSULTANT</p>		<p>PROJECT PHOTOS</p>

NOTES:

1. REFERENCE PLATE LAYOUT DIAGRAM FOR MOVEMENT CONTROL HOOK LOCATIONS.



MOVEMENT CONTROL HOOK DETAIL



MOVEMENT CONTROL HOOK PLACEMENT DETAIL



10/30/23

FOR APPROVAL

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as the work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY
C	9/8/2023	REVISED PER REVIEWER COMMENTS	JEM


CONTECH
ENGINEERED SOLUTIONS LLC
www.contechES.com
9100 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX

BridgeCor
CONTECH
CONTRACT
DRAWING

BRIDGECOR SINGLE RADIUS ARCH
45'-10" SPAN X 22'-11" RISE
TYONEK CREEK - COOK INLET
ANCHORAGE, AK

PROJECT No.	SEQ. No.	DATE
704132	010	3/11/2023
DESIGNED:	DRAWN:	
XXX	SCC	
CHECKED:	APPROVED:	
JAH	XXX	
SHEET No.	6	OF
		8

I:\PROJECTS\2023\10\30\23-10-11\20231030\BRIDGECOR\DRAWINGS\CONTRACT\PIE\N152R3RAC\CONC.DWG 8/30/2023 11:18 AM



SELECT GRANULAR STRUCTURAL BACKFILL LIMITS.



INITIAL LIFTS OVER THE CROWN OF STRUCTURE AS INDICATED BY SHADED AREA TO BE COMPACTED TO REQUIRED DENSITY WITH HAND OPERATED EQUIPMENT OR WITH LIGHTWEIGHT TRACTOR (D-4 OR LIGHTER) EQUIPMENT.

NOTES:

- MINIMUM SELECT GRANULAR STRUCTURAL BACKFILL WIDTH IS BASED ON AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS SECTION 12 AND/OR THE RESULTS OF THE PROJECT SPECIFIC FINITE ELEMENT ANALYSIS.
- ALL SELECT GRANULAR STRUCTURAL BACKFILL TO BE PLACED IN A BALANCED FASHION IN THIN LIFTS (8" LOOSE TYPICALLY) AND COMPACTED TO 90 PERCENT DENSITY PER AASHTO T-180.
- MONITORING OF THE SINGLE RADIUS ARCH STRUCTURE IS REQUIRED DURING THE BACKFILLING PROCESS, THE METHOD, FREQUENCY AND DURATION SHALL BE DETERMINED BASED ON THE SIZE AND SHAPE OF THE STRUCTURE.
- PREVENT DISTORTION OF SHAPE AS NECESSARY BY VARYING COMPACTION METHODS AND EQUIPMENT.
- PLACE SELECT GRANULAR STRUCTURAL BACKFILL IN RADIAL LIFTS AT APPROXIMATELY 75% OF THE RISE OF THE SINGLE RADIUS ARCH STRUCTURE.
- BECAUSE OF THE FLEXING AND VIBRATION OF THE CROWN PLATES, THE FULL COMPACTION DENSITY LEVELS OFTEN CAN NOT BE ACHIEVED IN THE FIRST SEVERAL INCHES OF FILL OVER THE CROWN.

BASED ON A PROJECT SPECIFIC ANALYSIS GAGE TO BE 3 BACKFILL MATERIAL TO BE A-1, COMPACTED TO 90% PER AASHTO T-180.

IF OTHER BACKFILL MATERIALS ARE TO BE EVALUATED, CONTACT YOUR LOCAL CONTECH REPRESENTATIVE.

SECTION

ADDITIONAL SELECT GRANULAR STRUCTURAL BACKFILL NOTES:

SATISFACTORY BACKFILL MATERIAL, PROPER PLACEMENT, AND COMPACTION ARE KEY FACTORS IN OBTAINING MAXIMUM STRENGTH AND STABILITY.

THE BACKFILL MATERIAL SHOULD BE FREE OF ROCKS, FROZEN LUMPS, AND FOREIGN MATERIAL THAT COULD CAUSE HARD SPOTS OR DECOMPOSE TO CREATE VOIDS. BACKFILL MATERIAL SHOULD BE WELL GRADED GRANULAR MATERIAL THAT MEETS THE REQUIREMENTS OF THE PROJECT SPECIFIC ANALYSIS NOTED BELOW. REFERENCE THE STRUCTURAL PLATE BACKFILL GROUP CLASSIFICATION TABLE ON THIS SHEET. RECYCLED CONCRETE/SLAG ARE NOT RECOMMENDED FOR STRUCTURAL BACKFILL MATERIAL. BACKFILL MUST BE PLACED SYMMETRICALLY ON EACH SIDE OF THE STRUCTURE IN 8" LOOSE LIFTS. EACH LIFT IS TO BE COMPACTED TO A MINIMUM OF 90% DENSITY PER AASHTO T-180.

A HIGH PERCENTAGE OF SILT OR FINE SAND IN THE NATIVE SOILS SUGGESTS THE NEED FOR A WELL GRADED GRANULAR BACKFILL MATERIAL TO PREVENT SOIL MIGRATION. IF THE PROPOSED BACKFILL IS NOT A WELL GRADED GRANULAR MATERIAL, A NON-WOVEN GEOTEXTILE FILTER FABRIC SHALL BE PLACED BETWEEN THE SELECT BACKFILL AND THE IN SITU MATERIAL.

DURING BACKFILL, ONLY LIGHTWEIGHT TRACKED VEHICLES (D-4 OR LIGHTER) SHOULD BE NEAR THE STRUCTURE AS FILL PROGRESSES ABOVE THE CROWN AND TO THE FINISHED GRADE. THE ENGINEER AND CONTRACTOR ARE CAUTIONED THAT THE MINIMUM COVER MAY NEED TO BE INCREASED TO HANDLE TEMPORARY CONSTRUCTION VEHICLE LOADS (HEAVIER THAN D-4).

STRUCTURAL PLATE BACKFILL GROUP CLASSIFICATION, REFERENCE AASHTO M-145

GROUP CLASSIFICATION	A-1-a	A-1-b
Sieve Analysis Percent Passing		
No. 10 (2,000 mm)	50 max.	---
No. 40 (0.425 mm)	30 max.	50 max.
No. 200 (0.075 mm)	15 max.	25 max.
Atterberg Limits for Fraction Passing No. 40 (0.425 mm)		
Liquid Limits	---	---
Plasticity Index	6 max.	6 max.
Usual Materials	Stone Fragment, Gravel and Sand	

*Modified from AASHTO M-145.

Fine beach sands, windblown sands, stream deposited sands, etc., exhibiting fine, rounded particles and typically classified by AASHTO M-145 as A-3 Materials should not be used.

If 95% compaction per AASHTO T-180 is specified, the backfill material shall be A-1-a.

Reference the most current version of ASTM D2487, Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System), for comparable soil groups.

FOR APPROVAL



10/30/23

I:\PROJECTS\2023\10\30\23-118\BRIDGECOR\DRAWINGS\CONTRACT\PIPER\1526\BRAC\CONC.DWG 8/30/2023 11:18 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as the work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY
C	9/8/2023	REVISED PER REVIEWER COMMENTS	JEM




www.conteches.com
9100 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX



CONTECH CONTRACT DRAWING

BRIDGECOR SINGLE RADIUS ARCH
45'-10" SPAN X 22'-11" RISE
TYONEK CREEK - COOK INLET
ANCHORAGE, AK

PROJECT No.	SEQ. No.	DATE
704132	010	3/11/2023
DESIGNED:	DRAWN:	
XXX	SCC	
CHECKED:	APPROVED:	
JAH	XXX	
SHEET No.	7 OF 8	



BRIDGECOR CORRUGATION PROFILE





PLATE LAP DETAIL



TYPICAL BOLTING DETAIL




PLATE LAPPING DETAIL (LOOKING DOWNSTREAM)



10/30/23

FOR APPROVAL

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as the work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY
C	9/8/2023	REVISED PER REVIEWER COMMENTS	JEM



www.ContechES.com
 9100 Centre Pointe Dr., Suite 400, West Chester, OH 45069
 800-338-1122 513-645-7000 513-645-7993 FAX



BRIDGECOR SINGLE RADIUS ARCH
 45'-10" SPAN X 22'-11" RISE
 TYONEK CREEK - COOK INLET
 ANCHORAGE, AK

PROJECT No.	SEQ. No.	DATE
704132	010	3/11/2023
DESIGNED	DRAWN	
XXX	SCC	
CHECKED	APPROVED	
JAH	XXX	
SHEET No.	8	OF
		8

I:\PROJECTS\2023\10\30\10301030\BRIDGECOR\DRAWINGS\CONTRACT\PIPER\NH15BR13RAC\CONC.DWG 8/30/2023 11:18 AM

**Conditional Use Permit
Anadromous Waters Habitat Protection District
Staff Report**

KPB File No.	2024-02
Planning Commission Meeting:	January 22, 2024
Applicant	Tyonek Tribal Council
Mailing Address	101 W Benson Blvd Suite 501 Anchorage, AK 99503
Legal Description	T 11N R 11W SEC 14 SM AN PORTION NW1/4 SEC 14 LYING SOUTH OF AREA KNOWN AS TYONEK CHIP MILL & CAMP FACILITY EXCLUDING USS 194 TRACT A
KPB Parcel Number	211-153-08

Project Description

A Conditional Use Permit is sought pursuant to KPB 21.18 for the construction of replacing a culvert and adding fill to the roadway within the 50-foot Habitat Protection District of the Tyonek Creek, as established in KPB 21.18.040.

Background Information

The current culvert at this location is undersized and is preventing fish passage. In order to put the necessary size culvert in place, the road must be brought up to grade and fill placed around the culvert on both sides. This project will replace the failing culvert and redirect the stream into the historical channel, as the stream has moved significantly since the culvert was installed. Removal of debris around the culvert inlet will help prevent future blocking of the culvert and a root wad revetment barrier will keep the stream in the channel. There will be 484 cubic yards of rip rap placed at the culvert inlet to keep erosion from the road bank. Revegetation will include; 740 square yards of vegetative mat, 765 plantings of shrubs and trees, and re-seeding around the disturbed area.

Project Details within the 50-foot Habitat Protection District

1. Placement of 400 linear feet of root wads.
2. Placement of a 120 foot long, 45'-10" x 22'-11" single radius multiplate arch pipe culvert.
3. Placement of 484 cubic yards of rip rap.
4. Placement of 1490 cubic yards of additional fill.

Findings of fact pursuant to KPB 21.18.081 Conditional Use Permit

1. Portions of this proposed project are within the 50-foot habitat protection district as defined by KPB 21.18.040.
2. Pursuant to KPB 21.18.081(B)(5), construction of transportation and utility infrastructure may be approved as a conditional structure/use within the habitat protection district.

3. Pursuant to 21.18.081(D) General Standards, staff finds that the proposed project meets the five general standards.
4. Pursuant to KPB 21.18.020(A), this chapter was established to protect and preserve the stability of anadromous fish through controlling shoreline alterations and disturbances along anadromous waters and to preserve nearshore habitat.
5. Pursuant to KPB 21.18.20(B)(5), one purpose of this chapter was established to separate conflicting land uses.
6. The current culvert is undersized and is preventing fish passage in the stream.
7. The road bed itself must be brought up to grade to allow the placement of the larger culvert with the addition of fill.
8. Pursuant to KPB 21.06.081(D)(3), the proposed work will occur on the applicant's property and shall not have an adverse effect on adjoining properties.
9. Kenai Peninsula Borough Planning Commission Resolution 2015-35 defines water-dependent as:
"...a use or structure located on, in or adjacent to water areas because the use requires access to the waterbody. The definition is applicable to facilities or activities that must be located at or near the shoreline and within the 50-foot buffer. An activity is considered water dependent if it is dependent on the water as part of the intrinsic nature of its operation. Examples of water dependent facilities may include, but are not limited to, piers, boat ramps, and elevated walkways."
10. The River Center found the application complete and scheduled a public hearing for January 22, 2023.
11. Agency review was distributed on January 10, 2024. No comments or objections have been received from resource agencies to date.
12. Pursuant to KPB 21.11.030, public notice was mailed to all property owners within a radius of 300 feet of the project on January 10, 2024. A total of 3 mailings were sent.
13. Pursuant to KPB 21.11.020, public notice was published in the Peninsula Clarion on January 10, 2024 and January 17, 2024.
14. The applicant is currently in compliance with Borough permits and ordinances.

Permit Conditions

1. Construction techniques and best management practices shall be utilized to ensure that land disturbing activities do not result in runoff or sedimentation to the Tyonek Creek.
2. The culvert must be designed and installed to meet KPB floodplain requirements.
3. The permittee shall minimize damage to all vegetation and shall revegetate all disturbed areas with native vegetation.
4. For each tree removed, two seedlings less than 5.5-feet tall of a species native to the region will be planted within the 50-foot HPD.
5. Storage or use of fuel is prohibited within 50-feet of any open water.
6. The River Center shall be notified at least 3 days prior to the start of the project.
7. If changes to the approved project described above are proposed prior to or during its siting, construction, or operation, the permittee is required to notify the River Center to determine if additional approval is required.
8. The permittee shall be held responsible for the actions of the contractors, agents, or others who perform work to accomplish the approved plan.
9. The construction or installation phase of this Conditional Use Permit must be completed within three calendar years from the date of the permit's issuance, or the Conditional Use Permit shall expire unless the Planning Commission finds that more time is necessary to effectuate the purposes of this chapter, in which case the commission may extend the deadline for a maximum of six years from the date of issuance. Prior to its expiration date and upon written request, the Planning Director may grant a Conditional Use Permit extension for 12 months (KPB 21.18.081 (H)).

- 10. In addition to the penalties provided by KPB 21.18.110, and pursuant to KPB 21.50, the permit may be revoked if the permittee fails to comply with the provisions of this chapter or the terms and conditions of a permit issued under this chapter. The Borough Clerk shall provide at least 15 day’s written notice to the permittee of a revocation hearing before the hearing officer (KPB 21.18.082).
- 11. The permittee shall comply with the terms, conditions and requirements of the Kenai Peninsula Borough Code of Ordinances Chapter 21.18, and any regulations adopted pursuant to this chapter.
- 12. The permittee is responsible for abiding by all other federal, state, and local laws, regulations, and permitting requirements applicable to the project (KPB 21.18.081 (G)).

General Standards

Pursuant to 21.18.081(D) General Standards, the following standards shall be met before conditional use approval may be granted:

- 1. The use or structure will not cause significant erosion, sedimentation, damage within the habitat protection district, an increase in ground or surface water pollution, and damage to riparian wetlands and riparian ecosystems; **Conditions 1-3 and Findings 1-4 appear to support this standard.**
- 2. Granting of the conditional use shall be consistent with the purposes of this chapter, the borough comprehensive plan, other applicable chapters of the borough Code, and other applicable planning documents adopted by the borough; **Condition 12 and Finding 4-5 appear to support this standard.**
- 3. The development of the use or structure shall not physically damage the adjoining property; **Finding 8 appears to support this standard.**
- 4. The proposed use or structure is water-dependent; **Finding 6-7, 9 appears to support this standard.**
- 5. Applicant’s or owner’s compliance with other borough permits and ordinance requirements; **Conditions 12 and Finding 14 appear to support this standard.**

Attachments

Multi-Agency Application
Draft Resolution 2024-02

Recommendation

Based on the findings, staff finds that the proposed project meets the five general standards of KPB 21.18.081. The Planning Commission could consider additional permit conditions to mitigate for any habitat loss if it chooses.

Staff recommends the Planning Commission grant a Conditional Use Permit for the proposed project details subject to adopted conditions as set forth in 2024-02.

Note: An appeal of a decision of the Planning Commission may be filed to the Hearing Officer, in accordance with the requirements of the Kenai Peninsula Borough Code of Ordinances, Chapter 21.20.250. An appeal must be filed with the Borough Clerk within 15 days of date of the notice of the decision using the proper forms and be accompanied by the filing and records preparation fee.

END OF STAFF REPORT



Donald E. Gilman River Center

514 Funny River Road, Soldotna, Alaska 99669 • (907) 714-2460 • (907) 260-5992 Fax

A Division of the Planning Department

Peter A. Micciche
Borough Mayor

KENAI PENINSULA BOROUGH PLANNING COMMISSION NOTICE OF PUBLIC HEARING

The Kenai Peninsula Borough received an application for a Conditional Use Permit under KPB 21.18.081 for a project within the 50-foot Habitat Protection District (HPD) of Tyonek Creek. This project has been scheduled for a public hearing before the Kenai Peninsula Borough Planning Commission.

Why are you receiving this notice?

Per code, property owners within 300 feet of the proposed project must receive notice of the public hearing. This project is located on Timber Road, Tyonek Alaska, Parcel ID 21115308. Our records indicate that you are a property owner within 300 feet of that parcel.

Project Description:

Tyonek Tribal Council is requesting to replace a failing culvert and add gravel to level the road within the 50-foot HPD of Tyonek Creek

How can you look at the application?

The meeting packet will be posted the week prior to the meeting. Once it has been posted it can be viewed at <https://kpb.legistar.com/Calendar>.

How do you attend the Planning Commission meeting?

When: Monday, January 22, 2024 at 7:30 p.m.
Where: Betty Glick Conference Room, George Navarre Building, 144 N Binkley St Soldotna AK
Zoom: Meeting ID 907 714 2200
<https://us06web.zoom.us/j/9077142200>
1-888-788-0099 or 1-877-853-5247

How do I comment on the project?

You can provide verbal comment at the meeting (see information above). You may also submit written comments. **Written comments must be received by 1:00 pm Friday, January 19, 2024.**

Mail comments to:
Donald E. Gilman River Center
514 Funny River Road
Soldotna, Alaska 99669

Email comments to:
planning@kpb.us
KenaiRivCenter@kpb.us

For additional information, please contact Morgan Aldridge at maldridge@kpb.us or (907) 714-2465.

KENAI PENINSULA BOROUGH PLANNING COMMISSION

RESOLUTION 2024-02

**A RESOLUTION GRANTING A CONDITIONAL USE PERMIT PURSUANT TO KPB 21.18 FOR THE
CULVERT REPLACEMENT AND PLACEMENT OF FILL WITHIN THE 50-FOOT HABITAT
PROTECTION DISTRICT OF TYONEK CREEK.**

- WHEREAS,** Chapter 21.18 provides for the approval of Conditional Use Permits for certain activities within the habitat protection district; and
- WHEREAS,** KPB 21.18.081 provides that a conditional use permit is required for construction not meeting the standards of KPB 21.18.071; and
- WHEREAS,** KPB 21.18.091 provides for mitigation measures by the planning department staff to address impacts to the Habitat Protection District from a proposed, ongoing, or completed project; and
- WHEREAS,** public notice was sent to all property owners within a 300-foot radius of the proposed activity as provided in Section 21.11.030; and
- WHEREAS,** public notice was published in the Peninsula Clarion on January 10, 2024 and January 17, 2024 as provided in Section 21.11.020; and
- WHEREAS,** public testimony was received at the January 22, 2023 meeting of the Kenai Peninsula Borough Planning Commission;

**NOW, THEREFORE, BE IT RESOLVED BY THE PLANNING COMMISSION OF THE KENAI
PENINSULA BOROUGH:**

That the Planning Commission makes the following findings of fact pursuant to KPB 21.18:

Section 1. Project Details Within the 50-foot Habitat Protection District

1. Placement of 400 linear feet of root wads.
2. Placement of a 120 foot long, 45'-10" x 22'-11" single radius multiplate arch pipe culvert.
3. Placement of 484 cubic yards of rip rap.
4. Placement of 1490 cubic yards of additional fill.

Section 2. Findings of fact pursuant to KPB 21.18.081

1. Portions of this proposed project are within the 50-foot habitat protection district as defined by KPB 21.18.040.
2. Pursuant to KPB 21.18.081(B)(5), construction of transportation and utility infrastructure may be approved as a conditional structure/use within the habitat protection district.
3. Pursuant to 21.18.081(D) General Standards, staff finds that the proposed project meets the five general standards.

4. Pursuant to KPB 21.18.020(A), this chapter was established to protect and preserve the stability of anadromous fish through controlling shoreline alterations and disturbances along anadromous waters and to preserve nearshore habitat.
5. Pursuant to KPB 21.18.20(B)(5), one purpose of this chapter was established to separate conflicting land uses.
6. The current culvert is undersized and is preventing fish passage in the stream.
7. The road bed itself must be brought up to grade to allow the placement of the larger culvert with the addition of fill.
8. Pursuant to KPB 21.06.081(D)(3), the proposed work will occur on the applicant's property and shall not have an adverse effect on adjoining properties.
9. Kenai Peninsula Borough Planning Commission Resolution 2015-35 defines water-dependent as:
"...a use or structure located on, in or adjacent to water areas because the use requires access to the waterbody. The definition is applicable to facilities or activities that must be located at or near the shoreline and within the 50-foot buffer. An activity is considered water dependent if it is dependent on the water as part of the intrinsic nature of its operation. Examples of water dependent facilities may include, but are not limited to, piers, boat ramps, and elevated walkways."
10. The River Center found the application complete and scheduled a public hearing for January 22, 2024.
11. Agency review was distributed on January 10, 2024. No comments or objections have been received from resource agencies to date.
12. Pursuant to KPB 21.11.030, public notice was mailed to all property owners within a radius of 300 feet of the project on January 10, 2024. A total of 3 mailings were sent.
13. Pursuant to KPB 21.11.020, public notice was published in the Peninsula Clarion on January 10, 2024 and January 17, 2024.
14. The applicant is currently in compliance with Borough permits and ordinances.

Section 3. Permit Conditions

1. Construction techniques and best management practices shall be utilized to ensure that land disturbing activities do not result in runoff or sedimentation to Tyonek Creek.
2. The culvert and fill must be designed and installed to meet KPB floodplain requirements.
3. The permittee shall minimize damage to all vegetation and shall revegetate all disturbed areas with native vegetation.
4. For each tree removed, two seedlings less than 5.5-feet tall of a species native to the region will be planted within the 50-foot HPD.
5. Storage or use of fuel is prohibited within 50-feet of any open water.
6. The River Center shall be notified at least 3 days prior to the start of the project.
7. If changes to the approved project described above are proposed prior to or during its siting, construction, or operation, the permittee is required to notify the River Center to determine if additional approval is required.
8. The permittee shall be held responsible for the actions of the contractors, agents, or others who perform work to accomplish the approved plan.
9. The construction or installation phase of this Conditional Use Permit must be completed within three calendar years from the date of the permit's issuance, or the Conditional Use Permit shall expire unless the Planning Commission finds that more time is necessary to effectuate the purposes of this chapter, in which case the commission may extend the deadline for a maximum of six years from the date of issuance. Prior to its expiration date and upon written request, the

Planning Director may grant a Conditional Use Permit extension for 12 months (KPB 21.18.081 (H)).

10. In addition to the penalties provided by KPB 21.18.110, and pursuant to KPB 21.50, the permit may be revoked if the permittee fails to comply with the provisions of this chapter or the terms and conditions of a permit issued under this chapter. The Borough Clerk shall provide at least 15 day's written notice to the permittee of a revocation hearing before the hearing officer (KPB 21.18.082).
11. The permittee shall comply with the terms, conditions and requirements of the Kenai Peninsula Borough Code of Ordinances Chapter 21.18, and any regulations adopted pursuant to this chapter.
12. The permittee is responsible for abiding by all other federal, state, and local laws, regulations, and permitting requirements applicable to the project (KPB 21.18.081 (G)).

Section 4. Pursuant to 21.18.081(D) General Standards, the following standards shall be met before conditional use approval may be granted:

1. The use or structure will not cause significant erosion, sedimentation, damage within the habitat protection district, an increase in ground or surface water pollution, and damage to riparian wetlands and riparian ecosystems; **Conditions 1-3 and Findings 1-4 appear to support this standard.**
2. Granting of the conditional use shall be consistent with the purposes of this chapter, the borough comprehensive plan, other applicable chapters of the borough Code, and other applicable planning documents adopted by the borough; **Condition 12 and Findings 4-5 appear to support this standard.**
3. The development of the use or structure shall not physically damage the adjoining property; **Finding 8 appears to support this standard.**
4. The proposed use or structure is water-dependent; **Findings 6-7, 9 appear to support this standard.**
5. Applicant's or owner's compliance with other borough permits and ordinance requirements. **Condition 12 and Finding 14 appears to support this standard.**

THIS CONDITIONAL USE PERMIT EFFECTIVE ON _____ DAY OF _____, 2024.

Jeremy Brantley, Chairperson
Planning Commission

ATTEST:

Ann Shirnberg
Administrative Assistant

Note: An appeal of a decision of the Planning Commission may be filed to the hearing officer, in accordance with the requirements of the KPB Code of Ordinances, Chapter 21.20.250. An appeal must be filed with the Borough Clerk within 15 days of date of the notice of the decision using the proper forms and be accompanied by the filing and records preparation fee.